

## Austin Drive Resurfacing

**Austin Drive:** US 224 to Willard West 4,050ft. x 16ft. (Avg.) = 7,200 SY

Tack Coat- Wedge .1 Gal/SY Overlay .05Gal/SY

4' Wedge on outside edge of both lanes. Average 1". 16' wide overlay entire road, 1.5" average

Ref.	Item	Description	Quant.	Unit	Price	Costs
1	103.5	Premium Contract Bond	1	LS	\$1,500.00	\$1,500.00
2	253	Full depth Pavement Repair 4", As per plan	265	SY	\$50.00	\$13,250.00
3	407	Tack Coat (Non- tracking)	750	GAL	\$3.00	\$2,250.00
4	441	Asphalt Concrete Surface, Type 1, Wedge, As per plan, (4' @ 1.5" edges)	150	CY	\$165.00	\$24,750.00
5	441	Asphalt Concrete, Surface, Type 1, 1.5", Avg. As per plan, PG64-22 , (1" @ Crown)	300	CY	\$160.00	\$48,000.00
6	614	Maintaining Traffic	1	LS	\$3,000.00	\$3,000.00
7	617	Stabilized Crushed Aggergate (411 berm)	110	CY	\$60.00	\$6,600.00
8	624	Mobilization	1	LS	\$4,000.00	\$4,000.00
9	Spec.	Butt Joints	2	EA	\$400.00	\$800.00
10	Spec.	Contingencies	1	LS	\$5,850.00	\$5,850.00
					<b>TOTAL</b>	<b>\$110,000.00</b>