

**Wakeman Township  
Chip and Seal - MC 3000**

**Various Township Roads:**

Average 0.36 Gal/SY - MC 3000 and 22 lbs of #8 washed limestone

**Total Project = 56,000 SY (5.7 Miles)**

Ref.	Item	Description	Quant.	Unit	Unit Cost	Total Cost
1	103.5	Premium Contract Bond	1	LS	\$500.00	\$500.00
2	441	Seal Coat Bituminous Material, MC 3000 @ 0.36 avg. gal/SY, as per plan	21,000	GAL	\$3.40	\$71,400.00
3	422	Seal Coat Aggregate #8 Washed Limestone @ 22lbs/SY avg., as per plan	620	TN	\$50.00	\$31,000.00
4	614	Maintaining Traffic, as per plan	1	LS	\$5,000.00	\$5,000.00
5	624	Mobilization	1	LS	\$1,000.00	\$1,000.00
6	Spec.	Contingencies	1	LS	\$1,100.00	\$1,100.00

**Total = \$110,000.00**

