

**Huron County Engineer's Office**  
**Chip and Seal - Phase 2 Estimate (Township Road Program)**

**Various Township Roads:**

Average 0.38 CRS-2 and 22 lbs of #8 washed limestone

**Total Project = 192,000 SY (19.8 Miles)**

Ref.	Item	Description	Quant.	Unit	Unit Cost	Total Cost
1	103.5	Premium Contract Bond	1	LS	\$4,000.00	\$4,000.00
2	441	Seal Coat Bituminous Material, CRS-2 @ 0.38 avg. gal/SY, as per plan	73,000	GAL	\$3.00	\$219,000.00
3	422	Seal Coat Aggregate #8 Washed Limestone @ 22lbs/SY avg., as per plan	2,200	TN	\$45.00	\$99,000.00
4	614	Maintaining Traffic, as per plan	1	LS	\$35,000.00	\$35,000.00
5	624	Mobilization	1	LS	\$10,000.00	\$10,000.00
8	Spec.	Contingencies	1	LS	\$3,000.00	\$3,000.00

**Total = \$370,000.00**

