

2026 Chip and Seal Phase 1

Bid Opening: Friday, February 6, 2026 9:00 a.m.

Ref.	Item	Description	Quant.	Unit	Unit Cost	Total Cost	Sarver Paving Co.		Melway Paving		Erie Blacktop, Inc.		Geauga Highway Co.	
1	103.5	Premium Contract Bond	1	LS	\$ 8,000.00	\$ 8,000.00	\$ 10,409.00	\$ 10,409.00	\$ 5,000.00	\$ 5,000.00	\$ 5,000.00	\$ 5,000.00	\$ 9,000.00	\$ 9,000.00
2	441	Seal Coat Bituminous Material, CRS2-P @ 0.40 avg. gal/SY, as per plan	212,500	GAL	\$ 3.10	\$ 658,750.00	\$ 2.65	\$ 563,125.00	\$ 2.55	\$ 541,875.00	\$ 3.25	\$ 690,625.00	\$ 2.92	\$ 620,500.00
3	422	Seal Coat Aggregate #8 Washed Limestone @ 22lbs/SY avg., as per plan	5,800	TN	\$ 45.00	\$ 261,000.00	\$ 43.17	\$ 250,386.00	\$ 53.75	\$ 311,750.00	\$ 40.00	\$ 232,000.00	\$ 60.37	\$ 350,146.00
4	614	Maintaining Traffic, as per plan	1	LS	\$ 58,000.00	\$ 58,000.00	\$ 74,851.00	\$ 74,851.00	\$ 75,000.00	\$ 75,000.00	\$ 45,000.00	\$ 45,000.00	\$ 68,000.00	\$ 68,000.00
5	624	Mobilization	1	LS	\$ 15,000.00	\$ 15,000.00	\$ 24,103.00	\$ 24,103.00	\$ 25,000.00	\$ 25,000.00	\$ 15,000.00	\$ 15,000.00	\$ 56,000.00	\$ 56,000.00
6	642	Centerline Paint Markings, as per plan	44.5	MI	\$ 1,000.00	\$ 44,500.00	\$ 900.00	\$ 40,050.00	\$ 685.00	\$ 30,482.50	\$ 720.00	\$ 32,040.00	\$ 685.00	\$ 30,482.50
7	642	Edgeline Paint Markings, as per plan	61.7	MI	\$ 800.00	\$ 49,360.00	\$ 750.00	\$ 46,275.00	\$ 600.00	\$ 37,020.00	\$ 630.00	\$ 38,871.00	\$ 632.00	\$ 38,994.40
8	Spec.	Contingencies	1	LS	\$ 5,390.00	\$ 5,390.00	\$ 5,390.00	\$ 5,390.00	\$ 5,390.00	\$ 5,390.00	\$ 5,390.00	\$ 5,390.00	\$ 5,390.00	\$ 5,390.00
						TOTAL =	\$ 1,100,000.00	\$ 1,014,589.00	\$ 1,031,517.50	\$ 1,063,926.00	\$ 1,178,512.90			