

**Huron County Engineer's Office****Chip and Seal - Phase 1****Various County Roads:**

Average 0.40 CRS2-P and 22 lbs of #8 washed limestone

**Total Project = 530,250 SY (44.5 Miles)**

Ref.	Item	Description	Quant.	Unit	Unit Cost	Total Cost
1	103.5	Premium Contract Bond	1	LS	\$8,000.00	\$8,000.00
2	441	Seal Coat Bituminous Material, CRS2-P @ 0.40 avg. gal/SY, as per plan	212,500	GAL	\$3.10	\$658,750.00
3	422	Seal Coat Aggregate #8 Washed Limestone @ 22lbs/SY avg., as per plan	5,800	TN	\$45.00	\$261,000.00
4	614	Maintaining Traffic, as per plan	1	LS	\$58,000.00	\$58,000.00
5	624	Mobilization	1	LS	\$15,000.00	\$15,000.00
6	642	Centerline Paint Markings, as per plan	44.5	MI	\$1,000.00	\$44,500.00
7	642	Edgeline Paint Markings, as per plan	61.7	MI	\$800.00	\$49,360.00
8	Spec.	Contingencies	1	LS	\$5,390.00	\$5,390.00

**Total = \$1,100,000.00**

A blue ink signature of the name "Lee E. Tansey" is written in a cursive, flowing style, positioned below the seal.