

Norwalk Township

South Norwalk Road Resurfacing

South Norwalk Road: Old State Rd to Greenwich Milan Townline Rd - 14,000ft. x 20 ft. (Avg.) = 31,200 SY


Resurfacing will consist of a asphalt overaly with an average thickness of 1-1/4" of Type 1 asphalt at the crown of the roadway. An average thickness of 1-1/2" was calculated to compensate for any non-uniform areas in the pavement and rolled edges that are not corrected with the scratch/level course.

Scratch/level course will consist of a variable thickness at various locations as directed by the inspector.

Tack coat all areas at 0.1 Gal/SY.

Ref.	Item	Description	Quant.	Unit	Price	Costs
1	103.5	Premium Contract Bond	1	LS	\$2,500.00	\$2,500.00
2	407	Tack Coat @ 0.1 Gal/SY, Non- tracking	4,500	GAL	\$3.00	\$13,500.00
3	441	Scratch / Level, Type 1, PG64-22, as per plan	320	CY	\$195.00	\$62,400.00
4	441	Asphalt Concrete, Surface, Type 1, 1 1/2" Avg., As per plan, PG64-22	1,300	CY	\$165.00	\$214,500.00
5	614	Maintaining Traffic	1	LS	\$3,000.00	\$3,000.00
6	617	Stabilized Crushed Aggergate (411 limestone berm)	200	TN	\$50.00	\$10,000.00
7	624	Mobilzation	1	LS	\$5,000.00	\$5,000.00
8	642	Center Line	2.7	MI	\$700.00	\$1,890.00
9	642	Edge Line	5.4	MI	\$400.00	\$2,160.00
10	Spec.	Butt Joint	4	EA	\$300.00	\$1,200.00
11	Spec.	Contingencies	1	LS	\$3,850.00	\$3,850.00

TOTAL = \$320,000.00



Lee E. Tansey, P.S.

5/18/20
Date