

**Fitchville River Resurfacing**


Prospect Road to Cook Road

Paint markings from Prospect Road to 1,000 ft. north of SR 18 - 32,200 ft. (6.1 mi.)

15,000 ft (2.8 mi.) in length with an average width of 20 ft., 34,000 SY including Intersections

Asphalt surface overlay 1 1/2"(avg.)

Ref.	Item	Description	Quant.	Unit	Unit Cost	Total Cost
1	103.5	Premium Contract Bond	1	LS	\$3,000.00	\$3,000.00
2	254	Pavement Planning, Butt Joints (0" - 1 1/2"), as per plan	4	EA	\$500.00	\$2,000.00
3	407	Tack Coat @ 0.1 Gal/SY, non-tracking	3,400	GAL	\$3.00	\$10,200.00
4	441	Asphalt Conc. , Level/Scratch, Type 1, Variable, PG64-22, as per plan	100	CY	\$200.00	\$20,000.00
5	441	Asphalt Conc., Surface Course, Type 1, 1 1/4", PG64-22, as per plan	1,450	CY	\$195.00	\$282,750.00
6	614	Maintaining Traffic	1	LS	\$10,000.00	\$10,000.00
7	617	Stabilized Crushed Agg. (berm), as per plan	400	TN	\$60.00	\$24,000.00
8	623	Monument Boxes, Adjust to Grade	2	EA	\$500.00	\$1,000.00
9	624	Mobilization	1	LS	\$8,000.00	\$8,000.00
10	642	Center Line	6.1	Mile	\$1,000.00	\$6,100.00
11	642	Edge Line	12.2	Mile	\$700.00	\$8,540.00
12	Spec.	Contingencies	1	LS	\$4,410.00	\$4,410.00

**Total = \$380,000.00**

A handwritten signature in blue ink, appearing to read "Lee E. Tansey", written over the bottom portion of the professional seal.