

County Line 2 (Green Road) Resurfacing (Wakeman Township)

US20 north for 3,400 ft. x 19 ft. (Avg.) = 7,200 SY

1-1/4" average overlay. 1-1/2" calculated for profile correction

Ref.	Item	Description	Quant.	Unit	Unit Cost	Total Cost
1	103.5	Premium Contract Bond	1	LS	\$2,000.00	\$2,000.00
2	253	Full Depth Pavement Repair, 4", as per plan	100	SY	\$70.00	\$7,000.00
3	407	Tack Coat @ 0.1 Gal/SY, Non- tracking	1,000	GAL	\$3.00	\$3,000.00
4	441	Asphalt Concrete, Surface Course, Type 1, Scratch/Level, PG64-22, as per plan	110	CY	\$250.00	\$27,500.00
5	441	Asphalt Concrete, Surface Course, Type 1, 1-1/4" Avg., PG64-22, as per plan	300	CY	\$200.00	\$60,000.00
6	614	Maintaining Traffic	1	LS	\$5,000.00	\$5,000.00
7	617	Stabilized Crushed Aggregate (411 berm)	80	TN	\$70.00	\$5,600.00
8	624	Mobilization, as per plan	1	LS	\$5,000.00	\$5,000.00
9	Spec.	Butt Joints	2	EA	\$500.00	\$1,000.00
10	Spec.	Contingencies	1	LS	\$3,900.00	\$3,900.00

TOTAL = \$120,000.00

