

New State Road Resurfacing

New State Road: Peru Olena to North Fairfield Corp Limit - 18,500ft. x 20 ft. (Avg.) = 41,115 SY (1" Mill)

Total Project = 41,115 SY

Ref.	Item	Description	Quant.	Unit	Price	Costs
1	103.5	Premium Contract Bond	1	LS	\$3,000.00	\$3,000.00
2	253	Full Depth Pavement Repair, 6" (as directed)	300	SY	\$60.00	\$18,000.00
3	254	Pavement Planing, 1"	41,200	SY	\$1.75	\$72,100.00
4	254	Patching of Planed Surface, as per plan	200	TN	\$80.00	\$16,000.00
5	407	Tack Coat @ 0.1 Gal/SY Non-tracking	4,200	GAL	\$2.50	\$10,500.00
6	441	Asphalt Concrete, Surface, Type 1, 1 1/2", As per plan, PG64-22	1,800	CY	\$150.00	\$270,000.00
7	441	Asphalt Concrete, Surface, Type 1, 2", Avg. As per plan, PG64-22 , 75 EA (drives)	40	TN	\$125.00	\$5,000.00
9	614	Maintaining Traffic	1	LS	\$7,000.00	\$7,000.00
8	617	Stabilized Crushed Aggergate (berm)	350	CY	\$60.00	\$21,000.00
10	623	Monument Boxes Adjusted to Grade	2	EA	\$300.00	\$600.00
11	624	Mobilization	1	LS	\$5,000.00	\$5,000.00
12	630	Signs (OPWC) As Per Plan	2	EA.	\$250.00	\$500.00
13	630	Ground Mounted Support, Square Posts, 4ft stubs 2 1/2" 730.016	20	EA	\$40.00	\$800.00
13	630	Ground Mounted Support, Square Posts, 2" 730.016	214	FT	\$10.00	\$2,140.00
14	630	Sign Posts Reflectors (48")	14	EA	\$30.00	\$420.00
15	630	Sign, Flat Sheet (Warning)	52	SF	\$25.00	\$1,300.00
16	630	Sign, Flat Sheet (Regulatory)	32	SF	\$25.00	\$800.00
17	630	Sign, Flat Sheet (Road name)	11	SF	\$25.00	\$275.00
18	642	Center Line	3.5	Mile	\$800.00	\$2,800.00
19	642	Edge Line	7	Mile	\$500.00	\$3,500.00
20	642	Temporary Centerline Striping (2 applications)	7	Mile	\$6,815.00	\$47,705.00
21	Spec.	Contingencies	1	LS	\$12,160.00	\$11,560.00
TOTAL						\$500,000.00



A handwritten signature in blue ink that reads "Lee E. Tansey".