

Norwich Township

May 25, 2021

Scottwood Road Improvements - Phase 1**Scottwood Road:** Thomas to Bridge - Current roadway- 4,060LF x 11.5 ft. (Avg.)

This project consists of constructing full depth aggregate berm widening, the relocation of roadside ditches, and storm sewer installation. The widening is to 20' of aggregate with future paved road surface width of 18'.

Ref.	Item	Description	Quant.	Unit	Price	Costs
1	103.5	Premium Contract Bond	1	LS	\$2,000.00	\$2,000.00
2	201	Clearing & Grubbing	1	LS	\$2,000.00	\$2,000.00
3	202	Pipe Removed, 24" & Under	150	LF	\$15.00	\$2,250.00
4	203	Excavation	1,100	CY	\$17.25	\$18,975.00
5	203	Embankment	1,000	CY	\$17.25	\$17,250.00
6	304	Aggregate base added 6"	780	CY	\$60.00	\$46,800.00
7	411	Aggregate base added 2"	260	CY	\$60.00	\$15,600.00
8	601	Rock channel protection, Type D w/o filter	10	CY	\$60.00	\$600.00
9	611	4" conduit, Type C (707.33)	10	LF	\$10.00	\$100.00
10	611	6" conduit, Type C (707.33)	10	LF	\$15.00	\$150.00
11	611	8" conduit, Type C (707.33)	10	LF	\$20.00	\$200.00
12	611	12" conduit, Type B (707.33)	80	LF	\$60.00	\$4,800.00
13	611	12" conduit, Type C (707.33)	80	LF	\$50.00	\$4,000.00
14	611	ODOT 2-2B	1	EA	\$1,500.00	\$1,500.00
15	614	Maintaining Traffic	1	LS	\$2,000.00	\$2,000.00
16	623	Construction Staking	1	LS	\$1,500.00	\$1,500.00
17	624	Mobilization	1	LS	\$3,000.00	\$3,000.00
18	652	Placing Stockpiled Topsoil	650	CY	\$20.00	\$13,000.00
19	659	Seeding & mulching Class 1	5,800	SY	\$1.50	\$8,700.00
20	659	Commercial Fertilizer (19-19-19)	0.26	TN	\$800.00	\$208.00
21	Spec.	Mailbox support relocation	4	EA	\$150.00	\$600.00
22	Spec.	Contingencies	1	LS	\$8,767.00	\$8,767.00
					TOTAL =	\$154,000.00