

**Ridge Road Resurfacing - Phase 1**

Bridge 1,800 ft south of Peru Olena Rd. to Hasbrock Rd.: 2.5 mi (13,400 ft.) width varies from 18-21 ft.  
 Asphalt Level Course, with an Asphalt Surface Course 1 3/4" (Avg.) Overlay  
 Paint Markings from Townline 131 Rd. to Hasbrock Rd. , 2.5 miles

\* 1 1/2" at crown, 1 3/4" calculated

Ref.	Item	Description	Quant.	Unit	Unit Cost	Total Cost
1	103.5	Premium Contract Bond	1	LS	\$4,000.00	\$4,000.00
2	202	Concrete Drive Removal, as per plan	230	SY	\$50.00	\$11,500.00
3	204	Subgrade Compaction	230	SY	\$4.00	\$920.00
4	209	Linear Grading	500	FT.	\$2.00	\$1,000.00
5	253	Full Depth Pavement Repair, 6", as per plan	400	SY	\$65.00	\$26,000.00
6	253	Full Depth Pavement Repair/Widening, 6", as per plan	400	SY	\$65.00	\$26,000.00
7	254	Pavement Planning, Butt Joints (0" - 1 3/4"), as per plan	11	EA	\$1,000.00	\$11,000.00
8	254	Pavement Planning, (2"), as per plan	4,000	SY	\$2.00	\$8,000.00
9	304	Aggregate Base (6")	40	CY	\$100.00	\$4,000.00
10	407	Tack Coat @ 0.1 Gal/SY, non-tracking	4,000	GAL	\$2.50	\$10,000.00
11	441	Asphalt Conc. , Level/Scratch, Type 1, Variable, PG64-22, as per plan	150	CY	\$225.00	\$33,750.00
12	441	Asphalt Conc., Surface Course, Type 1, 1 3/4" (Avg.), PG64-22, as per plan	1,400	CY	\$200.00	\$280,000.00
13	441	Asphalt Conc., Intersections, Surface Course, Type 1, 1 3/4" (Avg.), PG64-22, as per plan	150	CY	\$250.00	\$37,500.00
14	441	Asphalt Conc., Drives Surface Course, Type 1, 3" (Avg.), PG64-22, as per plan	40	CY	\$350.00	\$14,000.00
15	441	Asphalt Conc., Inter. Course, Type 1, 1 3/4", PG64-22, as per plan	200	CY	\$195.00	\$39,000.00
16	614	Maintaining Traffic	1	LS	\$15,000.00	\$15,000.00
17	617	Stabilized Crushed Agg. (berm), as per plan	400	TN	\$60.00	\$24,000.00
18	623	Monument Boxes, Adjust to Grade	5	EA	\$500.00	\$2,500.00
19	624	Mobilization	1	LS	\$5,000.00	\$5,000.00
20	642	Center Line	2.5	Mile	\$1,200.00	\$3,000.00
21	642	Edge Line	5.0	Mile	\$800.00	\$4,000.00
22	644	Stop Bars, 24"	100	FT.	\$20.00	\$2,000.00
23	Spec.	Contingencies		LS	\$7,830.00	\$7,830.00

**Total = \$570,000.00**

