

Greenwich Milan Townline Road Resurfacing Phase 2

GMTL Road: Jennings Rd to TL 131 - 7750ft. x 18.5 ft. (Avg.) = 16,000 SY

Tack Coat- Pre-level .025gal/SY Overlay .05gal/SY

Ref.	Item	Description	Quant.	Unit	Price	Costs
1	103.5	Premium Contract Bond	1	LS	\$1,500.00	\$1,500.00
2	407	Tack Coat @ 0.025/0.05 Gal/SY Non-tracking	900	GAL	\$2.50	\$2,250.00
3	441	Asphalt Concrete Surface, Type 1, Scratch/Level, As per plan, (4.5' @ 3/4")	100	CY	\$165.00	\$16,500.00
4	441	Asphalt Concrete, Surface, Type 1, 1.5", Avg. As per plan, PG64-22 , (1" @ Crown)	670	CY	\$155.00	\$103,850.00
5	614	Maintaining Traffic	1	LS	\$3,000.00	\$3,000.00
6	617	Stabilized Crushed Aggergate (berm)	180	CY	\$60.00	\$10,800.00
7	624	Mobilization	1	LS	\$4,000.00	\$4,000.00
8	Spec.	Butt Joints	3	EA	\$400.00	\$1,200.00
9	Spec.	Contingencies	1	LS	\$6,900.00	\$6,900.00
					TOTAL	\$150,000.00



Lee E. Tansey