

Townline 131 Road Resurfacing

Towline 131 Road: Peru Center Rd to SR 61 - 9,000 ft. x 20 ft. (Avg.) = 20,000 SY
 1" average overlay. 1-1/4" calculated for profile correction

Total Project = 20,000 SY

Ref.	Item	Description	Quant.	Unit	Price	Costs
1	103.5	Premium Contract Bond	1	LS	\$1,500.00	\$1,500.00
2	407	Tack Coat @ 0.1 Gal/SY ,Non- tracking	2,200	GAL	\$2.50	\$5,500.00
3	441	Asphalt Concrete, Surface, Type 1, PG64-22 (Scratch/level, as directed), as per plan	70	CY	\$180.00	\$12,600.00
4	441	Asphalt Concrete, Surface, Type 1, 1" Avg., PG64-22 (Calculated at 1 1/4"), as per plan	700	CY	\$165.00	\$115,500.00
5	614	Maintaining Traffic	1	LS	\$3,000.00	\$3,000.00
6	617	Stabilized Crushed Aggregate Berm (#411)	170	CY	\$60.00	\$10,200.00
7	624	Mobilization	1	LS	\$4,000.00	\$4,000.00
8	642	Center Line	1.71	MI	\$1,000.00	\$1,710.00
9	Spec.	Butt Joints	3	EA	\$500.00	\$1,500.00
10	Spec.	Contingencies	1	LS	\$4,490.00	\$4,490.00
					TOTAL	\$160,000.00