

Huron County Engineer's Office
Chip and Seal - Phase 2 Estimate (Township Road Program)

Various Township Roads:

Average 0.38 CRS-2 and 22 lbs of #8 washed limestone

Total Project = 335,000 SY (33.5 Miles)

Ref.	Item	Description	Quant.	Unit	Unit Cost	Total Cost
1	103.5	Premium Contract Bond	1	LS	\$7,000.00	\$7,000.00
2	441	Seal Coat Bituminous Material, CRS-2 @ 0.38 avg. gal/SY, as per plan	127,000	GAL	\$3.10	\$393,700.00
3	422	Seal Coat Aggregate #8 Washed Limestone @ 22lbs/SY avg., as per plan	3,700	TN	\$40.00	\$148,000.00
4	614	Maintaining Traffic, as per plan	1	LS	\$45,000.00	\$45,000.00
5	624	Mobilization	1	LS	\$16,000.00	\$16,000.00
8	Spec.	Contingencies	1	LS	\$5,300.00	\$5,300.00

Total = \$615,000.00

