

Huron County Engineer's Office
Chip and Seal - Phase 2 Estimate (Township Road Program)

Various Township Roads:

Average 0.38 CRS-2 and 22 lbs of #8 washed limestone

Total Project = 117,000 SY (13.0 Miles)

Ref.	Item	Description	Quant.	Unit	Unit Cost	Total Cost
1	103.5	Premium Contract Bond	1	LS	\$4,000.00	\$4,000.00
2	441	Seal Coat Bituminous Material, CRS-2 @ 0.38 avg. gal/SY, as per plan	45,000	GAL	\$3.00	\$135,000.00
3	422	Seal Coat Aggregate #8 Washed Limestone @ 22lbs/SY avg., as per plan	1,300	TN	\$48.00	\$62,400.00
4	614	Maintaining Traffic, as per plan	1	LS	\$30,000.00	\$30,000.00
5	624	Mobilization	1	LS	\$10,000.00	\$10,000.00
6	Spec.	Contingencies	1	LS	\$3,600.00	\$3,600.00

Total = \$245,000.00

