

**Richmond Various Roads Resurfacing**

Pleasant Street from Washburn Road to dead end 1,200 feet  
 Broad Street from Willard Street to dead end 900 feet  
 Willard Street from Pleasant Street to Broad Street 360 feet  
 Grace Street from Pleasant Street to Broad Street 360 feet  
 Vine Street from Pleasant Street to Broad Street 360 feet

Ref.	Item	Description	Quant.	Unit	Unit Cost	Total Cost
1	103.5	Premium Contract Bond	1	LS	\$2,000.00	\$2,000.00
2	254	Butt Joints	1	EA	\$1,000.00	\$1,000.00
3	407	Tack Coat @ 0.1 Gal/SY, non-tracking	950	GAL	\$4.00	\$3,800.00
4	441	Asphalt Conc., Surface Course, Type 1, (1 1/4") PG64-22, as per plan	220	CY	\$225.00	\$49,500.00
5	441	Asphalt Conc., Level/Scratch, Type 1, Variable, PG64-22, as per plan	125	CY	\$235.00	\$29,375.00
6	614	Maintaining Traffic	1	LS	\$5,000.00	\$5,000.00
7	617	Stabilized Crushed Agg. (berm), as per plan	75	TN	\$65.00	\$4,875.00
8	624	Mobilization	1	LS	\$5,000.00	\$5,000.00
9	Spec.	Contingencies	1	LS	\$4,450.00	\$4,450.00

**Total = \$105,000.00**

