

Vernon Road Resurfacing

Vernon Road: US 224 to Bullhead 3,950ft. x 16ft. (Avg.) = 7,0000 SY

Tack Coat- Scratch/Level .1 Gal/SY Overlay .05 Gal/SY

Base Repair with Asphalt Concrete Intermediate Type 2 @ 4"

Scratch/Level full width. Zero at crown.

Ref.	Item	Description	Quant.	Unit	Unit Cost	Total Costs
1	103.5	Premium Contract Bond	1	LS	\$1,000.00	\$1,000.00
2	253	Pavement Repair 4", Type 2 Material, as per plan	400	SY	\$50.00	\$20,000.00
3	407	Tack Coat (Non- tracking)	1,000	GAL	\$3.00	\$3,000.00
4	441	Asphalt Concrete Intermediate, Type 2, Scratch/Level, as per plan, (At US 224 Intersection)	10	CY	\$190.00	\$1,900.00
5	441	Asphalt Concrete Surface, Type 1, Scratch/Level, as per plan	140	CY	\$195.00	\$27,300.00
6	441	Asphalt Concrete, Surface, Type 1, as per plan, PG64-22, (1" @ Crown)	290	CY	\$180.00	\$52,200.00
7	614	Maintaining Traffic	1	LS	\$3,000.00	\$3,000.00
8	617	Stabilized Crushed Aggergate (411 berm)	75	CY	\$70.00	\$5,250.00
9	624	Mobilization	1	LS	\$4,000.00	\$4,000.00
10	Spec.	Butt Joints	2	EA	\$400.00	\$800.00
11	Spec.	Contingencies	1	LS	\$6,550.00	\$6,550.00

TOTAL \$125,000.00

