

**Wakeman Township  
Chip and Seal Estimate**

**Various County Roads:**

Average 0.36 MC 3000 and 22 lbs of #8 washed limestone

**Total Project = 47,000 SY (4.4 Miles)**

Ref.	Item	Description	Quant.	Unit	Unit Cost	Total Cost
1	103.5	Premium Contract Bond	1	LS	\$1,000.00	\$1,000.00
2	441	Seal Coat Bituminous Material, MC-3000 @ 0.36 avg. gal/SY, as per plan	17,000	GAL	\$3.50	\$59,500.00
3	422	Seal Coat Aggregate #8 Washed Limestone @ 22lbs/SY avg., as per plan	520	TN	\$45.00	\$23,400.00
4	614	Maintaining Traffic, as per plan	1	LS	\$3,000.00	\$3,000.00
5	624	Mobilization	1	LS	\$2,000.00	\$2,000.00
6	Spec.	Contingencies	1	LS	\$1,100.00	\$1,100.00

**Total = \$90,000.00**



A handwritten signature in blue ink, appearing to read "Lee E. Tansey", written over the bottom portion of the professional engineer seal.